



# U.S. EPA Local Climate & Energy Webcast Energy Efficiency in Water and Wastewater Facilities

October 30, 2013

Michael DiBara  
Project Manager, MassDEP  
[www.mass.gov/dep](http://www.mass.gov/dep)



# Water / Wastewater Treatment in MA

- 370 public facilities
- \$150M / year

## Impacts

- 1 billion kWhs
- 1 million tons (CO<sub>2</sub>)



# A New Public / Private Partnership



## Public

- (7) Water & (7) Wastewater Facilities
- MA Dept. of Environmental Protection
- MA Executive Office of Energy / Environmental Affairs
- MA Dept of Energy Resources
- EPA New England
- MA Renewable Energy Trust
- University of MA – Northeast CHP Center

## Private

- Every Major Investor-Owned Electric & Gas Utility

## Non Profit

- Consortium for Energy Efficiency

# Massachusetts' Energy Pilot

(2007 – 2010)



- Advance energy efficiency
- Advance clean energy
- A working model

**Goal: 20% reduction in costs & CO<sub>2</sub> emissions**

# Massachusetts Energy Management Pilot for Wastewater and Drinking Water Facilities

*A Targeted Approach to Advance Municipal Energy Savings and Greenhouse Gas Reductions*

## Pilot Facilities



These projects are being made possible by the collaborative efforts of the following organizations:

- Executive Office of Energy & Environmental Affairs
- MassDEP
- Massachusetts Division of Energy Resources
- University of Massachusetts Amherst
- Center for Energy Efficiency and Renewable Energy
- EPA New England
- Massachusetts Technology Collaborative
- Renewable Energy Trust
- Utility / Energy Efficiency Providers: NETA, National Grid/KeySpan, Cape Light Compact, Western Massachusetts Electric, United Bay State Gas, and Berkshire Gas
- Committee on Energy Efficiency

# 14 Pilot Facilities



Efficiency: **Save \$2M / Year**



Green Power: **Save \$1.7M / Year**

# ARRA – Green Infrastructure

Recovery & Reinvestment:

Clean Energy & the Environment

Jump-start “Green” projects: 20% of SRF ARRA



Fully Implement Energy Pilot & Other “Green” projects

(7) Wastewater Plants:	<b>\$42.6M</b>
(7) Water Plants:	<b><u>\$ 8.2M</u></b>
	<b>\$50.8M</b>
(7) Others	<b><u>\$17.8M</u></b>
<b>Total</b>	<b>\$68.6M</b>



CITY OF PITTSFIELD  
**WASTEWATER TREATMENT PLANT UPGRADES**  
FUNDED THROUGH MASSACHUSETTS DEP'S  
CLEAN WATER STATE REVOLVING FUND (CWSRF) PROGRAM &  
AMERICAN RECOVERY AND REINVESTMENT ACT (ARRA)

<b>BAR RACK REPLACEMENT</b> \$1,860,000 CONTRACTOR: R.H. WHITE AUBURN, MA	<b>AERATION UPGRADES</b> \$2,371,863 CONTRACTOR: C.H. NICKERSON TORRINGTON, CT
<b>COMBINED HEAT &amp; POWER</b> \$1,919,000 CONTRACTOR: R H. WHITE AUBURN, MA	<b>PHOTOVOLTAIC INSTALLATION</b> \$7,324,682 CONTRACTOR: NEXAMP NORTH ANDOVER, MA

ENGINEER: KLEINFELDER/S E A  
ROCKY HILL, CT



# Results

- **Save \$5+M / year for ratepayers**
- **34% annual reduction in energy costs and CO<sub>2</sub> emissions**
- **10+ megawatts of “green” power**
  - 5.2 MW (solar), 4.8 MW (wind)
  - .34 MW (CHP), .20 MW (hydro)
- **Zero-net energy pathway**


# MA Energy Leaders




- Coalition of state, federal, community & energy efficiency providers (Mass Save®)
- Each meeting has a technical presentation, a presentation from a utility, a discussion on energy management planning, and a site visit.

# Drinking Water and Wastewater Plants and Districts

## Working with MassDEP, DOER, and U.S. EPA to Address Energy Use



0 4 8 16 Miles



Map provided by DOER  
7-23-11, jpfister

# Reducing Operating Costs & Reinvesting in your Facility



CLEANENERGYRESULTS  
program

Getting  
More

Achieving Positive Cash Flow  
through Energy Saving Upgrades  
at Water Infrastructure Facilities



MASSACHUSETTS  
CLEAN ENERGY  
CENTER

- *Quantify energy & cost savings*
- *Energy-savings can boost your bottom line & reduce your carbon footprint*
- *Pay for wasted energy or reinvest it in your facility (people / equipment / assets)*



**Thank You!**

**Michael DiBara, Project Manager**  
**(508) 767-2885**  
**[Michael.dibara@state.ma.us](mailto:Michael.dibara@state.ma.us)**



**GREATER LAWRENCE SANITARY DISTRICT  
ENERGY EFFICIENCY PROGRAM  
2000-2013**

**U.S. EPA Local Climate & Energy Webcast  
Energy Efficiency in Water and Wastewater  
Facilities**

**October 30, 2013**

Presented by:

Richard E. Weare, GLSD Capital Projects Manager

# GLSD WWTP SYSTEM



- **MEMBER COMMUNITIES**
  - Lawrence, Methuen, Andover, No. Andover, Dracut, MA & Salem, NH
- **Wastewater Treatment Plant**
  - Design Capacity - 52 MGD
  - “Wet Weather” Peak Flow Capacity - 135 MGD
  - Based on CSO LTCP increase wet weather pumping to 167 MGD
  - Peak Secondary Flow Capacity - 126 MGD
- **Pumping Station**
  - 2 - 800 h.p. Pumps and 2 – 1250 h.p. Pumps
- **Sludge Drying Facility**
  - 2 Process Trains rated at 19 dry tons/day each




# GLSD ENERGY EFFICIENCY STUDY PLANS

- Energy Evaluation Audit – 1995
  - No Action on 1995 Evaluation
- Biosolids Improvement Study - 1998
- Lighting System Evaluation – 2001
- Secondary Treatment System Evaluation – 2004
  - Replace Mechanical Aeration with Fine Bubble Diffusers and Anaerobic Selector – Completed in 2006
- Renewable Energy Assessment - 2008
- Comprehensive Energy Evaluation Audit – 2009
  - Participated in the DEP Energy Management Pilot Program
  - Phase 1 Construction Completed in 2010 with ARRA Stimulus Funds
- Lighting System Evaluation – 2009
- Primary and Secondary Energy Evaluation - 2012


# SCOPE OF 2009 ENERGY AUDIT

- A Comprehensive Energy Evaluation Audit was performed which provided specific energy improvement recommendations
- Identified Energy Use and Cost Components
- Cost Effective Energy Savings Recommendations:
  - GLSD Operational Measures
    - 5 Low Cost Operational Measures Identified
  - GLSD Energy Conservation Measures
    - 18 Conservation Measures Identified
  - GLSD Energy Supply Measures
    - 2 Supply Measures Identified
- GLSD uses the EPA Plan-Do-Check-Act system for its Energy Program


# Electric Energy Use




# GLSD WWTF Electric Energy Breakdown



# 2007 GLSD Natural Gas Use



# 2007 Digester Gas Use



# 2009 ENERGY AUDIT STUDY

## ESTIMATED SAVINGS

- Electricity
  - kWh Savings <sup>(1)</sup> : 4,537,062
  - kW Savings <sup>(2)</sup> : 550
  - Electric Cost Savings: \$ 636,963
- Natural Gas
  - MMBtu Saved: 28,150
  - Natural Gas Savings <sup>(3)</sup>: \$ 349,624
- Reduced Emissions
  - Carbon Dioxide 2035 Tons
  - Methane 349 lbs.
  - Nitrous Oxides 73 lbs.

(1) Based on \$0.1343/kWh;

(2) Based on \$4.74/kW

(3) Based on \$12.42/MMBtu

# 2010 CONSTRUCTION PROJECT SCOPE

- Energy Efficiency Upgrade, Phase 1
  - 3 engineering firms/4 construction contracts:
    - Installed 23 VFD's to replace Eddy Current Clutches
    - Replaced 19 Motors with Premium Efficiency Motors
      - 25 h.p. to 125 h.p. units
    - WWTP Admin. Building EMS & HVAC Improvements
    - Pump Station HVAC Control System Improvements & installation of VFD and premium efficiency motor
    - Installed KW Meters to Track Energy Usage
    - Fine Bubble Aeration System Upgrade utilizing Motorized Air Valves
    - Upgraded Hot Water Condensate Pumps with VFD's
    - Replaced Plant Water Pumps and installed VFD's.

# 2010 CONSTRUCTION PROJECT

## SCOPE (continued):

- Energy Efficiency Upgrade, Phase 1
  - Installed New Energy Efficient Steam Boilers w/Dual Fuel Burners (Natural Gas & Digester Gas)
  - Lighting System Improvements
  - Installed 441 kW Photovoltaic Arrays.

# 2010 CONSTRUCTION PROJECT FUNDING

- Energy Efficiency Upgrade, Phase 1

Four Construction Contracts prepared under a “fast-track” design schedule to allow projects to be “shovel ready” and eligible for DEP’s AARA funding grants.

– ARRA Funding paid Construction Costs	\$4,922,384
– Utility Incentives paid Design Fees	\$ 693,084
– Net Cost to District	\$ 0
– Simple Payback without funding	2.9 years

# CONSTRUCTION PROJECT FUNDING 2000 - 2013

<u>YEAR</u>	<u>PROJECT</u>	<u>CONSTRUCTION COST</u>	<u>UTILITY INCENTIVE</u>	<u>DEP FUNDING</u>
2000	Biosolids Improvements, Contract 1	\$17,580,759	NAF	\$12,356,880
2000	Biosolids Heat Drying Facility	\$12,169,501	NAF	\$8,553,502
2003	Lighting System Upgrade - 2003	\$139,213	\$39,100	\$0
2006	Secondary Syst Upgrade - Fine Bubble Diffusers	\$19,162,497	\$750,000	2% Loan
2010	Energy Project, Contract 1 - PEM & VFD's	\$590,003	\$315,046	DEP-ARRA
2010	Energy Project, Contract 2 - HVAC	\$1,156,359	\$137,285	DEP-ARRA
2010	Energy Project, Contract 3 - PW & VFD's	\$531,400	\$381,083	DEP-ARRA
2010	Energy Project, Contract 4 - Solar System	\$1,976,172	\$0	DEP-ARRA
2010	Lighting Upgrade, Phase 1	\$99,613	\$23,947	\$0
2013	72" Force Main Replacement	\$11,265,786	N/A	2% Loan
2013	Primary Clarifier Baffles & Aeration Upgrade	\$2,136,712	\$350,203	2% Loan
2013	Lighting System Upgrade, Phase 2	\$118,399	\$9,530	\$0
	TOTALS	\$66,926,414	\$2,001,194	
				DEP GRANT
	Energy Projects Identified in 2009 Energy Audit			DEP 2% LOAN
			NAF = Not Applied For	

# CONSTRUCTION PROJECT SAVINGS 2000 - 2013

<u>YEAR</u>	<u>PROJECT</u>	<u>CONSTRUCTION COST</u>	<u>ANNUAL kWh/MMBTU SAVINGS</u>	<u>ANNUAL COST SAVINGS</u>	<u>PAYBACK (YRS)</u>
2000	Biosolids Improvements, Contract 1	\$17,580,759	-	↓	-
2000	Biosolids Heat Drying Facility	\$12,169,501	-	\$1,000,000	-
2003	Lighting System Upgrade	\$139,213	382,848	\$41,728	1.77
2006	Secondary Syst Upgrade - Fine Bubble Diffusers	\$19,162,497	3,314,607	\$287,376	1.52*
2010	Energy Project, Contract 1 - PEM & VFD's	\$590,003	464,280	\$65,309	0
2010	Energy Project, Contract 2 - HVAC	\$1,156,359	62,196/6067 **	\$83,600	0
2010	Energy Project, Contract 3 - PW & VFD's	\$531,400	474,105/5497**	\$135,010	0
2010	Energy Project, Contract 4 - Solar System	\$1,976,172	-	\$59,000+	0
2010	Lighting Upgrade, Phase 1	\$99,613	260,225	\$44,923	2.21
2013	72" Force Main Replacement (@165 mgd)	\$11,265,786	1,402,800	\$188,396	-
2013	Primary Clarifier Baffles & Aeration Upgrade	\$2,136,712	1,298,501	\$169,022	4.9
2013	Lighting System Upgrade, Phase 2	\$53,497	101,379	\$17,438	2.13
	TOTALS	\$66,926,414	7,760,941/11,564	\$2,091,802	
			* Based on \$1,170,000 Cost	Savings based on \$0.1343/kWh	
	Energy Projects Identified in 2009 Energy Audit		** kWh/MMBTU	Now: \$0.08355/kWh	

# D/B PHOTOVOLTAIC SYSTEM

## Capacity

- Area 1 & 2

- Ground Mount System (bid in 2010)
- kW Capacity:
- Number of PV Modules:

441.0

2100

Total D/B Bid Cost:

\$1,971,742

Cost per Watt

\$ 4.47

- In Comparison, ENR (8/19/2013)\* indicates:

- Installed PV Systems larger than 100 KW average \$4.60 per watt
- Utility-scale PV projects prices ranged from \$2.30 to \$6.80 per watt

\* Data from Berkeley National Laboratory

# PHOTOVOLTAC SOLAR SYSTEM

- The Solar System will save GLSD approximately \$59,000 per year in Electricity Costs based on \$0.106 per kW
- Solar Renewable Energy Certificates are available to GLSD to sell on the Open Market [2012 REC sale equaled \$32,280]
- GLSD Solar Array generates enough electricity to power the equivalent of approximately 80 Massachusetts homes



# FUTURE PROJECTS

- Pump Station – 2 New 800 h.p & 2 new 1250 h.p. Pumps & VFD's
  - Est. kWh Savings: 1,722,326
  - Est. Electric Cost Savings: \$239,474
- Future CSO LTCP Projects and other project designs will always have energy savings initiatives included
- EPA's Plan-Do-Check-Act system says always look to improve

# CLEAN ENERGY FOR OUR KIDS FUTURE

