

# Lincoln County, WV Onsite Treatment Project Overview



# Issues

- o Significant bacterial contamination in the tributaries of the Left Fork watershed of the Mud River
- o Rural, low income area
  - o Area MHI - \$19,120
- o Property not suitable to traditional systems
  - o Lot size too small
  - o Unable to perc., etc...



# Bigger Picture

- o Project Director meant for this project to be a case study into issues involving rural wastewater treatment issues.
- o These issues included, but were not limited to:
  - Impacts of pharmaceuticals & mineral content on wastewater.
  - Making systems become more affordable.
  - Improve training of O&M professionals in emerging technologies.
  - Ensure that direct discharge systems met E.coli limits.





The Counties and County Seats of  
**West Virginia**  
25 0 25 50 Miles

**LINCOLN**  
Hamlin











# Solution

- o 117 Individual onsite systems
- o Multiple phases from 2004 - 2015
- o Total cost \$4,116,734
- o Average cost per system - \$23,445
- o Initial phase in 2004 was funded by an EPA Grant
- o Remaining phases covered by CWSRF debt forgiveness - Starting with ARRA

# Results

## Dog Bone Creek that empties into the Left Fork

- o Prior to Phase 3 Installation
  - o E. coli: > 200,000; 40,000; 7,500; 50,000
- o Post Installation
  - o E. coli: 450, 250, 360
  
- o Summer recreational project for area children on June 15, 2016 since the area lake from the left fork watershed is clean enough to swim in.



# Community Support

- o 200 area residents participated in monthly meetings, designed criteria for eligibility and served on bidding committees
- o Projects were sponsored by the Lincoln County Commission
- o Creation of a Wastewater Management Association for long-term system maintenance

# Logistical Considerations

## o Site Concerns

- Can you get to the home (roads, bridges, terrain, ROW)?
- Is open space available (trash, abandoned items, etc.)?
- Will it be located too close to well (min. 50' gap must be maintained)?
- Close to discharge point?
- Is the water table high?



# Logistical Considerations

## o Utilities

- Electrical – Is it available & up to code?
- Plumbing – Is it is accessible, up to code, or exist at all?
- Upgrades were funded for systems to function properly as part of this project.

# Phase I Systems/Processes

- o 6 types of systems were installed to evaluate their effectiveness to lower E.coli levels
  - o Pureflo Peat
  - o Sand filtration
  - o HAU
  - o Eco Peat
  - o Geotextile
  - o Septic w/low pressure pipe subsurface discharge
- o After sampling, the results showed Pureflo's system was the best & would be installed exclusively in the future phases.

**NOTE:** Orenco system wasn't tested in this Phase & would later be installed in Phase V.



# Phase I Systems/Processes


- o As time & usage began to mount, problems with most of the systems began to occur.
- o Some couldn't meet limits, others had functional problems.
- o These issues eventually caused replacement of individual components and/or complete system replacement as part of subsequent phases.

# Typical Post-Phase I Installation

- o Included the following:
  - Septic Tank (primary treatment).
  - Effluent Tank w/ Pump.
  - Pureflo peat modules (secondary treatment).
  - Trojan UV (disinfection).
  - Direct discharge.



# Typical Puraflo schematic



# Pureflo Peat Module









# Ashco UV Unit





# Direct Discharge w/ Permit Sign





# Lessons Learned

- o Due to I/I, the Commission stopped using concrete tanks.
- o Education is required for homeowners. For example, trying to teach homeowners not to dispose of kitchen grease into the onsite system.
- o Antibiotics and/or cancer treatments adversely effect the treatment system.
- o Additional training is needed for system installers and maintenance providers.
- o Construction and engineering oversight is a must.



# Concrete Tanks

- Were used in Phase I, but almost immediately had problems.
- Holes developed allowing water both in and out.
- Manufacturer wasn't willing or able to completely satisfy the Commission with his attempts at solving issues.
- Commission had to switch to polyethylene tanks and exclude Manufacturer's products from being used in the project.

















# Phase V


- o By Phase V, the eligibility rules had to be modified to handle issues that arose from other Phases
- o These new rules stated home had to:
  - Be occupied before a certain date.
  - Be a permanent, full time residence.
  - Have a failing, existing system.
  - Be habitable.
  - Join the Maintenance Association.
- o Orenco Systems were the primary technology installed



# Orenco AdvanTex System

## Components of a Residential AdvanTex® Treatment System (Mode 1) Listed by Flow Path

- 1 Two Chamber Processing Tank
- 2 Biotube® Pump Vault
- 3 Biotube Filter
- 4 Effluent Pump
- 5 Discharge Assembly
- 6 AdvanTex® AX20 Filter Pod
- 7 Recirculating Splitter Valve (RSV)
- 8 Float Switches
- 9 External Splice Box
- 10 VeriComm® Control Panel





# Installed Orenco System





# Long term concerns/issues

- o Are rates sufficient enough to maintain required level of service?
- o What is the sustainability of the systems?
- o Will homeowners continue to support the maintenance association?
- o Eventually, plan is that O&M will be taken over by a PSD.

# Contact Information

- o Ric MacDowell : [ricmacdowell@gmail.com](mailto:ricmacdowell@gmail.com)
- o Jeff Brady, WV DEP: [Jefferson.E.Brady@wv.gov](mailto:Jefferson.E.Brady@wv.gov)
- o Kathy Emery, WV DEP:  
[Katheryn.D.Emery@wv.gov](mailto:Katheryn.D.Emery@wv.gov)
- o Site Website:  
<http://www.lincolncountywv.org/WastewaterProject/ContactInfo/tabid/209/Default.aspx>





**QUESTIONS?**